

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37 N.R. 24 W


Delta COUNTY

DESCRIPTION OF CORNER N 1/16 corner for sections 7/8

CORNER MONUMENT 1" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 11/1/68, F. J. Bray

WITNESSES TO CORNER..... 8" Tamarack (N 1/16) (BT) S 72° W, 48 links



6" B. Spruce (N 1/16) (BT) N 26° W, 21 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed midway and on line between section corner to north and 1/4 corner to south.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 12/11/68
REGISTERED LAND SURVEYOR
Frank J. Bray