

DELTA

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. _____ S., R. _____ E. _____ W. _____	_____
2. PROPERTY CONTROLLING IN SECTION <u>22</u> , T. <u>37</u> ,	N. _____ S., R. <u>24</u> E. _____ W. _____	<u>2</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____	N. _____ S., R. _____ E. _____ W. _____	_____
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, **David B. Babbitt** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on July 13 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

2 - East 1/16 corner on the north section line of Section 22. D.N.R. monument (by Frank Bray R.L.S.) 12" Cedar - N74°W - 74 lks.; 4" Dead Cedar - N50°E - 56 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

2 - Re-set Frank Bray's monument to true M.P.O.L. position as Frank's record says it was set. We found his monument 20.99' west of mid point. This situation was pointed out to us by M.P. Davis R.L.S. of Escanaba.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

2 - 1" pipe, 4" aluminum cap; 6" Bl. Ash - N39°W - 25.2'; 5" Cedar - S76°E - 19.6'; 10" Bl. Ash - N15°E - 32.2'; 4" Cedar - S58°W - 41.8'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 7-20-81
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558