

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 38-39 N.R. 18 W.


Delta COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 4, 5, 32, 33

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 9/8/60

WITNESSES TO CORNER.....5" Twin W. Birch (S 33 NBT) N 52° E 32 Links



9" Cedar (S 32 NBT) N 65° W 42 Links

12" W. Birch (S 4 NBT) S 30° E 26½ Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced 40.00 chains south of an original 1/4 corner between Sections 32 and 33 and by proportionate distance between corners east and west.

SURVEYOR'S SEAL

SIGNED Billy D. Buckley DATE 5/31/61
REGISTERED LAND SURVEYOR
Billy D. Buckley