

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 38-39 N.R. 18-19 W


Delta COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 1, 36, 31, 6
Also Township Corner

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 9/8/60

WITNESSES TO CORNER.....12" W. Pine (S 31 NBT) N 78° E 05 Links



14" H. Maple (S 1 NBT) S 41° W 13 Links

8" H. Maple (S 6 NBT) S 20° E 45 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-estabished by double proportioned measurement to Section

Corners 1 mile to west, north and south and Section corner 2 miles to east.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 5/31/61
REGISTERED LAND SURVEYOR
Billy D. Buckler