

SURVEY & REMONUMENTATION

JAN 14 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On October 31, 1997

Walter C. Thorne
Chairman

For corners in
DELTA
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>38 N</u> R <u>19 W</u>	<u>E-08 & E-09</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTERED Nov 5 1997
9:00 AM
8 Pgs 241
Walter C. Thorne

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims E-08 [W1/4 COR S21] E-09 [NW COR S28]

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, M.P. DAVIS, in a field survey on SEPTEMBER, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-08 [W1/4 COR S21] A.MERRYWEATHER, D.S. - 1848-WOOD POST- (BIRCH 08°-S54°E-09 LINKS) (BIRCH 08°-N50°W-22 LINKS)
M.S.McNABB-1920-ORIGINALS DESTROYED SET IRON BOLT 1/2 DIST BETWEEN CORNERS-BT STAKES NE & SW 33'

E-09 [NW COR S28] A.MERRYWEATHER, D.S.-1848-WOOD POST- (BIRCH 07°-S55°E-10 LINKS) (CEDAR 08°-N65°E-11 LINKS)
M.S.McNABB-1920-STAKE IN PLACE "ORIGINALS PLAIN" NO OTHER WIT'S NOTED

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-08 [W1/4 COR S.21] NO CORNER EVIDENCE FOUND. REESTABLISHED CORNER POSITION ON LINE WITH AND AT THE MIDPOINT BETWEEN SEC COR'S 1/2 MILE N & S. DISTANCE BETWEEN SEC COR'S CHECKS WELL WITH THE RECORDS OF McNABB.

E-09 [NW COR S.28] FOUND IN PLACE A 1/2" X 18" IRON PIN W/A T.OBRIEN SURVEY CAP. MR. OBRIEN INFORMED ME THAT HE HAD SET THE SAME FROM CORNER MONUMENTATION FOUND BY HIMSELF ALONG THE SOUTH LINE OF SEC 21. DISTANCES FROM THIS CORNER CHECK WELL TO McNABB'S CORNER FOUND 1 MILE TO THE WEST AND THE MASONARY NAIL 1 MILE TO THE NORTH. ACCEPTED THE EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-08 SET, 6" BELOW GRADE, A 5/8" X 18" REBAR W/A 3 1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION.

CEDAR 07"	MAPLE 22"	MAPLE 24"	C/L N-S COUNTY ROAD
N74°W	N28°E	S56°E	WEST
58.16'	37.33'	75.05'	13'

E-09 SET OVER EXISTING MONUMENT A BERNTSEN AINB30 ALUM MONUMENT WITH THE CAP STAMPED TO ID THE CORNER POSITION.

CEDAR 13"	CEDAR 08"	BALM OF GILEAD 08"	SURVEY MONUMENT SIGN POST
S21°E	S28°W	N24°E	N40°W
35.15'	43.52'	5.74'	2.17'

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC - DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. Davis Date 10/27/97
Surveyor's Michigan License No. 16926