

SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/12, 1996

Robert J. Doolittle
Acting Chairman

For corners in
DELTA
(County)

Located in: Corner Code #

- | | | | | |
|------------------------------------|--------|--------|------|------|
| 1. Public Land Survey | T 38 N | R 19 W | C-11 | R-11 |
| | T | R | | |
| | T | R | | |
| | T | R | | |
| 2. Property Controlling in Section | S | T | R | |
| | S | T | R | |
| 3. Miscellaneous Property in Sec. | S | T | R | |
| | S | T | R | |

Recorded DEC 20 1996
at 2:00 o'clock PM
Liber 8 Page 154
William C. Thoren
Delta County, Mich. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims
C-11 [SW COR S29] E-11 [NW COR S33]

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 15 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, M.P. DAVIS, in a field survey on NOVEMBER, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-11 [SW COR S29] WOOD POST - A.MERRYWEATHER, D.S. - 1848 (BIRCH 30"-S70°W-30 LINKS) (MAPLE 06"-N55°3'-06 LINKS)
- C.E. BROTHERTON-1878-CORNER IN PLACE-NO WIT'S OR DESCRIPTION OF MONUMENT GIVEN
- M.S. McNABB-1925-FOUND IRON STAKE IN ROAD "FROM PREVIOUS SURVEYS" (BIRCH 14"-N47°E-38.0')(MAPLE 16"-S38°W-34.75')
- M.DAVIS-1977-FOUND 2" IRON PIPE IN PLACE-ID FROM McNABB'S MAPLE BT SW STILL GREEN-REC'D LIBER 2 OF LCR'S PG 133 (TP-S88°W-32.0')

- E-11 [NW COR S33] WOOD POST-A.MERRYWEATHER, D.S.-1848 (SUGAR 12"-N34°E-21 LINKS) (BEECH 06"-S45°W-19 LINKS)
- M.S. McNABB-1916-FOUND 8 SIDED IRON STAKE IN PLACE-FENCE POST BT'S SW 46' & NORTH 28.3'
- J.ERICKSON-1972-SET 1/2" REBAR FROM RECORDS OF McNABB-NEW BT'S FENCE POSTS NORTH 20.0" & S45°E-43.8' (UNRECORDED)
- T.OBRIEN-1978-FOUND RR SPIKE IN PLACE-NOTED FENCE POST BT'S-S41°W-36.8' S54°E-39.55' N32°W-43.65' REC'D LIBER 2 OF LCR'S PG 207

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-11 [NW COR S.29] FOUND IN PLACE 2" IRON PIPE, ID CORNER POSITION FROM McNABB'S MAPLE BT SW STILL GREEN. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE POSITION OF THE ORIGINAL CORNER.
- E-11 [NW COR S33] FOUND IN PLACE AN EIGHT SIDED SOLID IRON PIN AS CALL FOR IN McNABB'S RECORDS. NO EVIDENCE FOUND OF O'BRIENS RR SPIKE. FOUND ERIKSON MONUMENT 6'N. & 3'W. OF McNABB'S COR. ACCEPTED EXISTING EIGHT SIDED MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-11 SET OVER EXISTING IRON PIPE A 5/8" X 18" REBAR W/A 3/4" ALUM CAP STAMPED TO ID THE CORNER POSITION & SET 6" BELOW RD GRADE.

| | | | |
|-------------------|-----------|--------------------|-----------|
| MAPLE 30"(OLD BT) | MAPLE 08" | DRILL HOLE IN ROCK | MAPLE 14" |
| S38°W | N.50°W | N36°E | S22°E |
| 35.55' | 65.98' | 45.30 | 83.70' |
- E-11 SET OVER EXISTING MON & 6" BELOW GRADE A 5/8" X 10" REBAR W/A 3/4" ALUM CAP STAMPED TO ID THE CORNER POSITION.

| | | |
|---------------------------|---------------------------------|---------------------------------|
| SURVEY MONUMENT SIGN POST | 3RD FENCE POST WEST OF COR POST | 3RD FENCE POST EAST OF COR POST |
| NORTH | N40°W | N52°E |
| 21.88' (TO FACE) | 43.18' | 37.47' |

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC - DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. Davis Date 12/10/96
Surveyor's Michigan License No. 16926

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983