

Approved By Delta Company  
 Land Survey Remonumentation  
 Peer Group Under Act 345 Of  
 P.A. of 1990 On DEC 23, 1999  
*Robert Schmeling*  
 Acting Chairman

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>DELTA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>38</u> NR <u>19</u> W	<u>I-01</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

RECORDED Feb 2 2000  
 AT 3:41 O'CLOCK PM  
 LIBER 9 PAGE 202  
*Wallace C. Thomas*  
 DELTA COUNTY MI REG. OF DEEDS  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, M.P. DAVIS, in a field survey on NOVEMBER, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

I-01 [NW COR SEC 2] A.MERRYWEATHER, D.S.-1848-WOOD POST (SUGAR 08" N22°E 14 LINKS)(SUGAR 08" S67°W 48 LINKS) BILLY D. BUCKLER-1961-FOUND IN PLACE A 3/4" IRON BAR AT ROA INTERSECTION, FROM WHICH (FENCE CORNER S36°W 44.2")(FENCE CORNER N42°W 47.4')(FENCE CORNER S40°E 40.9') RECORDED IN LIBER 3 OF LCR'S PAGE 213. GARY KOEPKE-1987-FOUND 3/8" IRON PIN IN ROAD INTERSECTION, ID FROM BUCKLER BT'S AND NOTED NEW BT'S (MAPLE 28" N55°E 57.63')(APPLE 09" S40°E 41.64')(PP S40°W 46.24')(FENCE POST N25°E 66.93')RECORDED IN LIBER 5 OF LCR'S PAGE 307.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-01 [NW COR SEC 2] FOUND IN PLACE A 1"(OD)I.P. AS DESCRIBED IN L.3 PG. 213 AND L.5 PG. 307 OF LCR'S. NO EVIDENCE OF 3/8" IRON PIN AS MENTIONED IN BOTH LCR'S. MAPLE BT AND PP BT ARE STILL VIABLE. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.

SURVEY &  
 REMONUMENTATION  
 FEB 10 2000  
 SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-01 SET, INSIDE OF EXISTING MONUMENT, A 5/8" X 18" REBAR W/A 3-1/4" ALUM CAP STAMPED TO ID THE CORNER POSITION.

YIELD SIGN POST	MAPLE 28"(OLD BT)	SURVEY MONUMENT SIGN POST	PP (OLD BT)
N27°W	N55°E	S36°E	S40°W
44.85'	57.63'	35.05'	46.24'

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC-DISTANCES ARE TO A NAIL W/A DELTA COUNTY REFERENCE TAG, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 12/20/99  
 Surveyor's Michigan License No. 16926