

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 38-39 N.R. 19 W


Delta COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 1, 2, 35, 36

CORNER MONUMENT 1/2" Iron Bar

DATE MONUMENT PLACED AND WITNESSED 9/7/60 with Frank J. Bray

WITNESSES TO CORNER.....5" Jack Pine (NBT) N 42° W 67 Links



Power Pole S 83° E 82 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from probable B.T. a White Pine bearing N 63° W, 45 Links
Found H. Maple Stump (a new bearing tree) N 70° W, 34 Links. This tree marked at
least 30 years ago. Corner lies on North edge of road to west and west edge of
road to north. Fences to west, south and roads to north check well with this corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 5/25/61
REGISTERED LAND SURVEYOR
Billy D. Buckler