

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 38-39 N.R. 19W


Delta COUNTY

DESCRIPTION OF CORNER Meander Corner for Sections 4-33

CORNER MONUMENT 1" Pipe with 4" Brass Cap.

DATE MONUMENT PLACED AND WITNESSED 9-29-61

WITNESSES TO CORNER..... 9" Cedar (M.C. NBT) S66°E 13.5 feet



9" Cedar (M.C. NBT) N50°E 20.0 feet

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was placed by extending alignment of $\frac{1}{4}$ Corner and Section Corner along North side of Section 4. No evidence of original Corner. Corner lies 5 feet from top edge of 150' limestone ledge.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE January 31, 1962
REGISTERED LAND SURVEYOR

Billy D. Buckler