

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. _____ S., R. _____ E. _____ W. _____	_____
2. PROPERTY CONTROLLING IN SECTION <u>9</u> , T. <u>38</u>	N. _____ S., R. <u>19</u> E. _____ W. _____	<u>1</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____	N. _____ S., R. _____ E. _____ W. _____	_____
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

DELTA
CO.

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on February 23 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

West 1/16 corner on the north section line; not previously recorded.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 3/8" iron rod buried in centerline of E-W road as shown on an old survey map by Billy D. Buckler R.L.S. dated 11-12-61. Witnessed existing iron rod.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/8" iron-rod buried in centerline of road
1" pipe, 4" aluminum cap - south - 233.00'; 6" cedar post - south - 33.2';
6" cedar post - north - 33.0'; power pole - S57°E - 117.3'; 3" balm of gilead -
N73°E - 105.9'

SEE SKETCH ON BACK OF PAGE

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558