

08/25

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Delta

(County)

Located In:

Corner Code #

- 1. Public Land Survey T ___ R ___
T ___ R ___
T ___ R ___
T ___ R ___
- 2. Property Controlling in Section S 4 T 38N R 19W 9.
- 3. Miscellaneous Property in Sec. S 4 T 38N R 19W Btw. 13 & 14.

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Babbitt, in a field survey on 4/30, 19 86, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

9. East 1/16 corner on East and West 1/4 line of Section 4. Not previously established.

wn.13. & 14. Property corner 621.5' east of the south 1/16 corner of Section 4. Not previously established.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

9. Set MPOL between the center of section and the East 1/4 corner of Section 4.

wn.13. & 14. Set on the E-W 1/16 line in the SE 1/4 of Section 4 at its intersection with the northwesterly ROW line of County Road 483.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 9. DNR Monument. Bwtn.13. & 14. DNR Monument.
 - 12" r. oak S11E, 13.65'
 - 8" sugar maple, S71E, 11.8'
 - 10" beech, N28E, 14.25'
 - 9" beech, N39W, 31.35'
 - DNR Monument East 176.3'
 - DNR Monument South 263.2'
 - 5" w. ash S75W, 26.65'
 - 4" w. ash N45W, 21.5'
 - 6" s. maple N29E, 13.3'
 - 5" s. maple S41E, 84.25'

See drawing on back of certificate.

Signed by David B. Babbitt Date 7-8-86

Surveyor's Michigan License No. RLS 21558