

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>38</u> N. <u>8.</u> R. <u>22</u> E. <u>W.</u>	MC A-3A MC A-4A
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

DELTA

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on September 4 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

A-3A

Original M.C. position
now under water in Green
Bay

A-4A

Original M.C. position
now under water in Green
Bay

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

A-3A

Found conc. mon. marking N.E. cor. of the plat of Portage Point—reported by R. Priniski C.E., surveyor of said plat, to be the same location as marked with an iron by surveyor Brotherton around 1920 to mark the sec. line between Sec. 7 T38N-R22W and Sec. 12 T28N-R23W.

A-4A

Projected a line from the W. $\frac{1}{4}$ cor. of sec. 6 across A-3A to near the southerly shore of Portage Point. This essentially fits method recorded in the original Gov't. survey and that described to me by R. Priniski, C.E., for the Brotherton survey, and the plat of Portage Point survey and fits *PLAT Mon. AS FOUND.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

All Bearings Magnetic

A-3A

$\frac{1}{2}$ " rod in 4" conc. mon.
4" ASH - N72°E - 45.1'
8" Birch (dead) - S53°W - 18.2'

A-4A

1" pipe and 4" aluminum cap incased in conc.
4" ash - N20°E - 26.2'
4" ash - S30°E - 24.6'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE 9-19-75
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558