

**SURVEY &  
REMONUMENTATION**

AUG 20 1996

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On June 27, 1996  
*Walter C. Thomas*  
Acting Chairman

For corners in  
DELTA  
(County)

Located In: Corner Code #

- |                                    |   |             |   |             |                |
|------------------------------------|---|-------------|---|-------------|----------------|
| 1. Public Land Survey              | T | <u>38 N</u> | R | <u>23 W</u> | <u>6</u> & C-5 |
|                                    | T |             | R |             |                |
|                                    | T |             | R |             |                |
|                                    | T |             | R |             |                |
| 2. Property Controlling in Section | S |             | T | R           |                |
|                                    | S |             | T | R           |                |
| 3. Miscellaneous Property in Sec.  | S |             | T | R           |                |
|                                    | S |             | T | R           |                |

Recorded 28 June 1996  
9:00 A.M. in Liber 8 Page 147  
*Walter C. Thomas* Reg. of Deeds.  
Delta County, Michigan  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_  
C-4 [W1/4 COR S8] C-5 [NW COR S17]

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

I, N.P. DAVIS, in a field survey on MARCH, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

C-4 [W1/4 COR S.8] WOOD POST - A.MERRYWEATHER, D.S. - 1847 (TAMARACK 08°-N48°E-06 LINKS) (CEDAR 07°-N38°W-28 LINKS) M.S.McNABB-1921-ID BY STAKE IN PLACE-NEW BT CEDAR 8" SW 9'

C-5 [NW COR S.17] WOOD POST - A.MERRYWEATHER, D.S. - 1847 (HEMLOCK 12°-S10°E-11 LINKS) (BIRCH 08°-N38°W-28 LINKS) NO RECORD EVIDENCE OF CORNER RECOVERY AND /OR SUBSEQUENT CORNER MONUMENTATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-4 [W1/4 COR S.8] NO CORNER EVIDENCE FOUND. ESTABLISHED CORNER POSITION ON LINE WITH AND AT MIDPOINT BETWEEN SECTION CORNERS N & S.

C-5 [NW COR S.17] FOUND IN PLACE A 3/4" IRON PIN & SQ'D CEDAR POST. NO EVIDENCE OF "GLO" BT'S. BLAZE LINES N-S & E-W FROM EXISTING CORNER MONUMENT. THIS MONUMENT APPEARS TO BE THE ONLY EVIDENCE AS TO THE LOCATION OF THE CORNER AND HAS APPARENTLY BEEN ACCEPTED, WITHOUT DISPUTE, BY THE ADJOINING LAND OWNERS. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-4 SET A 4" X 4" X 36" CONC. MONUMENT W/A 3" BRASS CAP STAMPED TO ID THE CORNER POSITION.  
 SPRUCE 5" CEDAR 6" CEDAR 6" CEDAR 6" SURVEY MONUMENT SIGN POST  
 N24°W N78°E S34°E S45°W EAST  
 12.36' 4.51' 1.92' 22.17' 3.03' (TO FACE)

C-5 REPLACED EXISTING MONUMENT W/A 4" X 4" X 36" CONC. MON W/A 3" BRASS CAP STAMPED TO ID THE CORNER POSITION.  
 HEMLOCK 12" HEMLOCK 12" HEMLOCK 9" HEMLOCK 15" SURVEY MONUMENT SIGN POST  
 N83°W N30°E S27°E S07°W EAST  
 36.05' 12.02' 8.31' 35.48' 2.64' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC - DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. Davis Date 6/19/96  
Surveyor's Michigan License No. 16926

