

**SURVEY &
REMONUMENTATION**

AUG 20 1996


COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On June 27, 1996
Phyllis B. Schumaker
Acting Chairman

For corners in
DELTA
(County)

Located In: _____ Corner Code # _____

- 1. Public Land Survey T 38 N R 23 W C-4 
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Recorded 28 June 1996
9:00 A.M. in Liber 8 Page 147
Walter C. Thorne Reg. of Deeds.
Delta County, Michigan
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____
C-4 [W1/4 COR S8] C-5 [NW COR S17]

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

I, M.P. DAVIS, in a field survey on MARCH, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
C-4 [W1/4 COR S.8] WOOD POST - A.MERRYWEATHER, D.S. - 1847 (TAMARACK 08°-N48°E-06 LINKS) (CEDAR 07°-N38°W-28 LINKS) M.S.McNABB-1921-ID BY STAKE IN PLACE-NEW BT CEDAR 8' SW 9'
- C-5 [NW COR S.17] WOOD POST - A.MERRYWEATHER, D.S. - 1847 (HEMLOCK 12°-S10°E-11 LINKS) (BIRCH 08°-N38°W-28 LINKS) NO RECORD EVIDENCE OF CORNER RECOVERY AND /OR SUBSEQUENT CORNER MONUMENTATION
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
C-4 [W1/4 COR S.8] NO CORNER EVIDENCE FOUND, ESTABLISHED CORNER POSITION ON LINE WITH AND AT MIDPOINT BETWEEN SECTION CORNERS N & S.
C-5 [NW COR S.17] FOUND IN PLACE A 3/4" IRON PIN & SQ'D CEDAR POST. NO EVIDENCE OF "GLO" BT'S, BLAZE LINES N-S & E-W FROM EXISTING CORNER MONUMENT. THIS MONUMENT APPEARS TO BE THE ONLY EVIDENCE AS TO THE LOCATION OF THE CORNER AND HAS APPARENTLY BEEN ACCEPTED, WITHOUT DISPUTE, BY THE ADJOINING LAND OWNERS. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
C-4 SET A 4" X 4" X 36" CONC. MONUMENT W/A 3" BRASS CAP STAMPED TO ID THE CORNER POSITION.

SPRUCE 5"	CEDAR 6"	CEDAR 6"	CEDAR 6"	SURVEY MONUMENT SIGN POST
N24°W	N78°E	S34°E	S45°W	EAST
12.36'	4.51'	1.92'	22.17'	3.03' (TO FACE)

C-5 REPLACED EXISTING MONUMENT W/A 4" X 4" X 36" CONC. MON W/A 3" BRASS CAP STAMPED TO ID THE CORNER POSITION.

HEMLOCK 12"	HEMLOCK 12"	HEMLOCK 9"	HEMLOCK 15"	SURVEY MONUMENT SIGN POST
N83°W	N30°E	S27°E	S07°W	EAST
36.05'	12.02'	8.31'	35.48'	2.64' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC - DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. Davis Date 6/19/96
Surveyor's Michigan License No. 16926