SURVEY & REMONUMENTATION

AUG 2 0 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On June 27, 1996
Colubbachmeling
acting Chairman

Filing Requirement of Act 74, Mich. P.A. 1970 or corners in DELTA Located In: Corner Code ## T 38 N R 23 W Public Land Survey 28 June 1996 R at9:00 o'clock A.M. in Liber __ R _ **Property Controlling** Τ_ R in Section Т Delta County, Michigan Miscellaneous Register of Deeds Stamp & File Number Property in Sec. _ , Recorded Plat Private Claims
K-3 [NW COR S.12] K-4 [W1/4 COR S.12] MAY/APRIL _, in a field survey on _ othereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned lines 1 and 2 above were in conformance with regulations and rules therefore as required in the arrent manual of survey instructions of the United States Department of the Interior, Bureau of Land lanagement or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 pove were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a ourt of Law; established, re-established, monumented, re-monumented, recovered, found as xpressed below: OTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate. escription of original monument and accessories and/or subsequent restoration: [NW COR S.12] WCOD POST - A.MERRYWEATHER.D.S. - 1847 - (TAMARACK 06"-N18"W-15 LINKS)(TAMARACK 08"-S15"E-06 LINKS) M.S.McNABB-1918-IRON STAKE IN PLACE - NO WIT'S GIVEN D.A.BROTHERTON-1921-IRON STAKE IN PLACE-NO WIT'S GIVEN-SET CONC. MON FOR PLAT OF PORTAGE ADD LIBER "B" OF PLATS PG 36 M.S.McNABB-1924-MONUMENT IN PLACE - NO WIT'S FRANK BRAY, RLS-1969-SPIKE IN BLK TOP OVER OBJECT THAT ATTRACTS NEEDLE-(PP-N41°E-48.2')(TELE POLE-873°E-95.0')(11/2" I.P. S. 33.1') REC'D LIBER 4 OF LCR'S PAGE 136. G.CARLSON, RLS-1979-FD 11/2" I.P. (PP-S71°E-95.17')(PP-S68'W-60.75)(PP-N44°E-48.46') REC'D L.2 LCR'S PG. 264. K-4 [W1/4 COR S.12] WOOD POST-A.MERRYWEATHER, D.S.-1847- (CEDAR 06"-N75"E-08 LINKS)(ELM 10"-WEST-22 LINKS) D.A.BROTHERTON-1921-EST 1/2 DIST BETWEEN COR'S-SET IRON STAKE-(W.BIRCH 12"-S82°W-33.6')(LITE POLE-S11°E-26.3') FRANK BRAY, RLS-1969-FD IRON PIN IN PLACE-(PP-S29°E-32')(HEMLOCK 18"-N59°E-41.2') REC'D L.4 OF LCR'S PAGE 72 Description of corner evidence found and/or method applied in restoring or reestablishing corner: K-3 [NW COR S.12] FOUND IN PLACE & FROST HEAVED TO COUNTY ROAD SURFACE A 2" IRON PIPE ENCASED IN A MICA 6" CONC. MONUMENT. THIS MONUMENT IS IN CONFLICT WITH G. CARLSON MON DESCRIPTION 3 1.2 OF LCR'S PG. 264. HOWEVER HIS B'RING & DIST TO THE PP NE CHECKS WELL. I IDENTIFIED THE EXISTING MONUMENT AS THAT SET BY BROTHERTON IN 1921 BY RETRACEMENT OF PORTIONS OF THE BOUNDARY OF THE PORTAGE ADD. AS REC'D M. P. LIBER *B* OF PLATS ON PAGE 36. ACCEPTED EXISTING MONUMENT AS THE BEST AVAILABLE EVIDENCE AS TO DAVIS THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER. LAND SURVEYOR X-4 [W1/4 COR S.12] NO EVIDENCE OF CORNER MONUMENT FOUND AS DESCRIBED ABOVE AS IT HAS APPARENTLY NO. BEEN DESTROYED IN RECENT CONSTRUCTION OF HWY. M-35. REESTABLISHED CORNER POSITION BY EXTENDING 16926 A LINE SOUTH FROM THE NW COR OF SEC. 12 THRU THE EXISTING N1/16 COR AND ESTABLISHING THE 1/4 CORNER ON THIS LINE AT A PROPORTIONATE DISTANCE SOUTH OF THE N1/16. AT THIS POINT I WAS ABLE TO LAND IDENTIFY BRAY'S HEMLOCK BT TO THE ME WHICH CHECKS WELL, THIS POSITION IS 1.28' EAST AND 0.13' NORTH OF THE MIDPOINT BETWEEN SEC COR'S N & S. ACCEPTED THIS POSITION AS BEING A CAREFUL & FAITH-FUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER. Description of monument for corner and accessories established to perpetuate locating the position of the corner: K-3 SET, INSIDE EXISTING MON, A 5/8" X 18" REBAR W/A 31/4" ALUM CAP STAMPED TO ID THE COR POSITION & RAISED TO GRADE W/A MON BOX. ASH 5" POWER POLE W.PINE 16" SPRUCE 5" ASH 5" N50°W N44°E S66°E SOUTH \$36°W 58.22' 48.46' (TO FACE) 84.31' 39.39 48.01' K-4 SET, INSIDE A MON BOX, A 5/8" X 18" REBAR W/A 31/4" ALUMN CAP STAMPED TO ID THE COR POSITION CEDAR 12" CEDAR 8" SURVEY MONUMENT SIGN POST N79°E \$47°E N82°W 51.051 64.201 58.28' (TO FACE) NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC - DISTANCES ARE TO A MAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE Signed by _ _ Date . Burveyor's Michigan License No. 📖 ENRIN APPROVED BY MICHIGAN STATE ROARD OF LAND SUBVEYORS, JAN. 28, 1971