

SURVEY & REMONUMENTATION

SEP 13 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On July 13, 1994

Robert A. Smiley
Acting Chairman

For corners in

DELTA (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>33 N</u> R <u>24 W</u>	<u>A-3/A-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Recorded Aug 12 1994

at 9:00 o'clock AM in Liber 8 Page 28

Walter C. Thorn
Reg. of Deeds.
Delta County, Michigan

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims A-3 [NW COR S7] A-4 [W1/4 COR S7]

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, M.P. DAVIS, in a field survey on JUNE, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-3 [NW COR S7] WOOD POST - JAMES H. MULLETTE, D.S. - 1848 (BEECH 4"-N61°W-12 LINKS) (BEECH 10"-S55°W-12 LINKS)
GEORGE ADAIR, D.S. - WOOD POST - 1852 (BEECH 13"-N78°E-12 LINKS) (BEECH 12"-S8°E-17 LINKS)
1982-M.D.O.T. RECORDS-FOUND 1" IRON PIN IN PLACE (POWER POLE-S60°W-42.46') (ELM 11"-S15°E-79.80') (RD SIGN POST-S45°E-47.72')

A-4 [W1/4 COR S7] WOOD POST - JAMES H. MULLETTE, D.S. - 1848 (CEDAR 12"-S34°W-21 LINKS) (CEDAR 12"-N42°W-31 LINKS)
1982-M.D.O.T. RECORDS-FOUND IRON PIN IN PLACE-(W.BIRCH 4"-S38°E-92.50') (CEDAR 9"-S55°E-73.01') (HEMLOCK 9"-EAST-70.29')
(POWER POLE-N45°E-71.7')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-3 [NW COR S.7] FOUND IN PLACE A 1" IRON PIN & BT'S AS MENTIONED IN 1982 M.D.O.T. NOTES OF THE RESURVEY OF HWY U.S. 2. CORNER MONUMENT IS AT THE C/L JCT OF C.R.'S. E-W & S & IN LINE WITH AN ANCIENT FARM FENCE TO THE NORTH. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.

A-4 [W1/4 COR S.7] FOUND IN PLACE A 5/8" IRON PIN & BT'S AS MENTIONED IN 1982 M.D.O.T. NOTES OF THE RESURVEY OF HWY. U.S. 2. CORNER MONUMENT IS 6' M/L WEST OF THE C/L OF THE N-S C.R. & 30" BELOW THE ROAD SURFACE. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE OF THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-3 SET, OVER EXISTING MON, A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE COR POSITION & RAISED TO RD SURFACE W/A MON.
SE COR OF HOUSE SURVEY MONUMENT SIGN POST ELM 16' POWER POLE
N22°W NORTH S15°E S60°W
114.30' 20.42' (TO FACE) 79.74' 42.46'

A-4 SET, OVER EXISTING MON & 6" BELOW RD SURFACE, A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION.
POWER POLE HEMLOCK 12" CEDAR 10" W.BIRCH 6" SURVEY MONUMENT SIGN POST
N45°E EAST S55°E S38°E WEST
71.70' 70.29' 79.01' 92.50' 11.85' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC - DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. Davis Date 9/10/94
Surveyor's Michigan License No. 16924