

**SURVEY & REMONUMENTATION**

SEP 13 1994

**LAND CORNER RECORDATION CERTIFICATE**

**COMMISSION**

Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On July 13, 1994  
*Robert Schmalzberg*  
Acting Chairman

For corners in  
DELTA  
(County)

Located In: Corner Code ##

1. Public Land Survey	T	38	N	R	24	W	A-5 & A-6
	T		R				
	T		R				
	T		R				
2. Property Controlling in Section	S		T		R		
	S		T		R		
3. Miscellaneous Property in Sec.	S		T		R		
	S		T		R		

Recorded Aug 12 1994  
at 9:00 o'clock AM in Liber 8 Page 29  
*William C. ...* Reg. of Deeds.  
Delta County, Michigan

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims A-5 [NW COR S18] A-6 [W1/4 COR S18]

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, M.P. DAVIS, in a field survey on JULY, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
 A-5 [NW COR S.18] WOOD POST - JAMES H. MULLETTE, D.S. - 1848 (SUGAR 12" -N9°W-20 LINKS) (SUGAR 12" -S60°W-36 LINKS)  
 GEORGE ADAIR, D.S. - WOOD POST - 1852 (LYNN 14" -N54°E-29 LINKS) (CEDAR 16" -S58°E-21 LINKS)  
 1982-M.D.O.T. RECORDS-FOUND IRON PIN IN PLACE (ELM 5" -N75°W-23.05') (RED PINE 14" -S80°E-28.71') (MAPLE 16" -S50°E-33.27') (ELM 5" -S30°W-48.22')  
 M.S. McNABB - 1946 - IRON STAKE IN PLACE - FENCE LINES E & W (NO OTHER BT'S NOTED)  
 A-6 [W1/4 COR S.18] WOOD POST - JAMES H. MULLETTE, D.S. - 1848 (CEDAR 8" -N72°W-26 LINKS) (CEDAR 6" -S65°W-31 LINKS)  
 NO RECORD EVIDENCE OF SUBSEQUENT CORNER RECOVERY OR MONUMENTATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 A-5 [NW COR S.18] FOUND IN PLACE IN LINE WITH FENCE LINES E & W A 1/2" IRON PIN AND BT'S IN PLACE AS NOTED IN 1982 M.D.O.T. FIELD NOTES OF RESURVEY OF HWY. U.S. 2. ACCEPTED EXISTING MONUMENT AS BEING THE SAME AS FOUND IN PLACE BY McNABB IN 1946 & AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.

A-6 [W1/4 COR S.18] FOUND IN PLACE, ORIGIN UNKNOWN, A 1" IRON PIPE. CORNER POSITION IS AT APPROX. C/L JCT OF C.R.'S. N-S & W AND IN LINE WITH AN ANCIENT FARM FENCE LINE TO THE EAST. NO OTHER EVIDENCE OF THE CORNER POSITION EXIST. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 A-5 SET, OVER EXISTING MON & 6" BELOW RD SURFACE, A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION.  
 RED PINE 18"      MAPLE 19"      SURVEY MONUMENT SIGN POST  
 S.80°E              S30°E              WEST  
 28.71'              33.27'              23.26' (TO FACE)  
 A-6 SET, OVER EXISTING MON & 6" BELOW RD SURFACE, A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION.  
 C/L N. END CMP X-PIPE      CEDAR 6"      CEDAR 5"      CEDAR 5"      SURVEY MONUMENT SIGN POST  
 N56°W              N62°E              S38°E              S48°W              EAST  
 26.02'              47.97'              48.44'              65.16'              24.73' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC - DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. Davis Date 7/11/94  
 Surveyor's Michigan License No. 16926

