

**SURVEY & REMONUMENTATION**

SEP 13 1994

**COMMISSION**

Approved By Delta County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On July 13, 1994  
*Walter C. Thayer*  
Chairman

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
DELTA  
(County)

Located In: Corner Code ##

1. Public Land Survey	T	<u>38</u> NR	<u>24</u> W	<u>A-7 &amp; A-8</u>
	T	R		
	T	R		
	T	R		
2. Property Controlling in Section	S	T	R	
	S	T	R	
3. Miscellaneous Property in Sec.	S	T	R	
	S	T	R	

Recorded Aug 12 1994  
at 9:00 o'clock AM in Liber 8 Page 30  
*Walter C. Thayer* Reg. of Deeds.  
Delta County, Michigan

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims A-7 [NW COR S19] A-8 [W1/4 COR S19]

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, M.P. DAVIS, in a field survey on JULY, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
A-7 [NW COR S.19] WOOD POST - JAMES H. MULLETTE, D.S. - 1848 (BIRCH 12"-S33°W-31 LINKS) (HEMLOCK 8"-N21°W-23 LINKS) GEORGE ADAIR, D.S. - WOOD POST - 1852 (HEMLOCK 22"-N71°E-23 LINKS) (HEMLOCK 30"-S60°E 27 LINKS) NO RECORD EVIDENCE OF SUBSEQUENT CORNER RECOVERY OR MONUMENTATION

A-8 [W1/4 COR S.19] WOOD POST - JAMES H. MULLETTE, D.S. - 1848 (SUGAR 1'4"-S59°W-14 LINKS) (CEDAR 6"-N63°W-19 LINKS) NO RECORD EVIDENCE OF SUBSEQUENT CORNER RECOVERY OR MONUMENTATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
A-7 [NW COR S.19] FOUND IN PLACE, ORIGIN UNKNOWN, A 1-1/4' I.P. IN LINE WITH ANCIENT FENCE LINE (DOWN AND IN POOR CONDITION), 2' M/L WEST OF THE C/L OF N-S COUNTY RD & 3' M/L SOUTH OF C/L OF COUNTY RD TO THE EAST. THIS POSITION FITS WELL WITH EXISTING FENCES AT THE 1/16 LINES N & S. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER. COR MONUMENT IS BADLY BENT & IN POOR CONDITION, APPARENTLY FROM RD MAINTENANCE.  
A-8 [W1/4 COR S.19] FOUND IN PLACE, ORIGIN UNKNOWN, A 1" I.P. IN LINE WITH A FARM FENCE LINE TO THE WEST & 6' M/L WEST OF THE C/L OF THE N-S COUNTY ROAD. THIS POSITION FITS WELL WITH EXISTING FENCES AT THE 1/16 LINES N & S. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER. COR MONUMENT IS BADLY BENT & IN POOR CONDITION, APPARENTLY FROM ROAD MAINTENANCE.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
A-7 REPLACED EXISTING MONUMENT, W/A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION.  
DRILL HOLE IN LARGE STONE    CEDAR 4"    STOP SIGN POST    SURVEY MONUMENT SIGN POST    POWER POLE  
N59°W    N43°W    N64°E    S42°E    S42°W  
19.48'    44.18'    66.88' (TO FACE)    41.39' (TO FACE)    31.96' (TO FACE)  
A-8 REPLACED EXISTING MONUMENT, W/A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION.  
SURVEY MONUMENT SIGN POST    DRILL HOLE IN LARGE STONE    NOTE: NO OTHER WIT'S AVAILABLE AS CORNER  
WEST    N36°E    POSITION IS SURROUND BY FARM FIELDS.  
10.96' (TO FACE)    41.95'

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC - DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. Davis Date 7/11/94  
Surveyor's Michigan License No. 16926