

SEP 13 1994

COMMISSION

Approved By Delta County Land Survey Remonumentation Peer Group Under Act 345 Of P.A. Of 1990 On July 13, 1994

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in DELTA (County)

Located In: Corner Code #/

Table with 3 columns: Description (Public Land Survey, Property Controlling, etc.), Township/Range (T 38 N R 24 W), and Corner Code (A-9, A-10).

Recorded Aug 12 1994 at 9:00 o'clock AM in Liber 8 Page 31

Walter S. Thomas Reg. of Deeds Delta County, Michigan

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat 5. Private Claims A-9 [NW COR S30] A-10 [W1/4 COR S30]

Grid table with columns A-L and rows 2-13, containing numbers 1-36.

I, M.P. DAVIS, in a field survey on JULY, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration: A-9 [NW COR S.30] WOOD POST - JAMES H. MULLETTE, D.S. - 1848 (HEMLOCK 18°-N27°W-16 LINKS) (CEDAR 8°-S69°W-17 LINKS) GEORGE ADAIR, D.S. - WOOD POST - 1852 (HEMLOCK 11°-N87°W-20 LINKS) (HEMLOCK 12°-S43°E 18 LINKS) M.S. McNABB-1915-FOUND STAKE IN PLACE, CLAIMED BY SETTLERS TO BE WHERE ORIGINAL STOOD - BT STAKES NW & SE 33' A-10 [W1/4 COR S.30] WOOD POST - JAMES H. MULLETTE, D.S. - 1848 (BEECH 12°-N10°W-30 LINKS) (FIR 8°-S48°W-31 LINKS) M.S. McNABB-1915-ESTABLISHED CORNER 1/2 DISTANCE BETWEEN CORNERS - BT STAKES NE & SW 33' F. BRAY-M.D.N.R.-1968-FOUND 1" IRON ROD IN E. WHEEL PATH OF GRAVEL ROAD (FENCE CORNER-N88°W-41 LINKS) (ASPEN 4°-S71°E-27 LINKS)

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: A-9 [NW COR S.30] FOUND IN PLACE A 1" IRON PIN AT THE APPROX C/L JCT OF COUNTY ROADS N-S & E-W. NO EVIDENCE OF McNABB'S 1915 BT STAKES FOUND. MEASUREMENTS SOUTH 1/2 MILE & 1 MILE TO EXISTING MONUMENTS CHECK WELL WITH McNABB'S RECORDS. ACCEPTED EXISTING MONUMENT AS BEING A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER. A-10 [W1/4 COR S.30] FOUND IN PLACE A 1" IRON PIN, SET IN 1915 BY M.S. McNABB, AT 1/2 DISTANCE BETWEEN CORNERS. NO EVIDENCE OF HIS 1915 BT STAKES FOUND THIS DATE. CORNER MONUMENT WAS IN 1968 BY FRANK BRAY (NICH D.N.R.) & HIS BT'S ARE STILL IN PLACE & GREEN. ACCEPTED EXISTING MONUMENT AS BEING A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: A-9 SET, OVER EXISTING MON, A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION. ELM 16" SURVEY MONUMENT SIGN POST BASSWOOD 6' ELM 12" N47°W N51°E S42°E S26°W 63.36' 43.67' (TO FACE) 56.91' 66.10' A-10 SET, OVER EXISTING MON, A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION. GATE POST MAPLE 7" MAPLE 6" MAPLE 7" SURVEY MONUMENT SIGN POST N26°W N68°E S27°E S69°W EAST 41.95' (TO FACE) 37.83' 50.41' 34.58' 13.40' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC - DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. Davis Date 7/11/94

Surveyor's Michigan License No. 16926