

**SURVEY & REMONUMENTATION COMMISSION**

SEP 13 1994

**COMMISSION**

Approved By Delta County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On July 13, 1994  
*John W. Kowalski*  
Acting Chairman

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
DELTA  
(County)

Located In: Corner Code ##

1. Public Land Survey	T <u>38 N</u> R <u>24 W</u>	<u>B-5 &amp; B-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Recorded Aug 12 1994  
at 9:00 o'clock AM in Liber 8 Page 35  
*William C. Thum*  
Reg. of Deeds.  
Delta County, Michigan

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims B-5 [N1/4 COR S.18] B-7 [N1/4 COR S.19]

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, M.P. DAVIS, in a field survey on JULY, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
B-5 [N1/4 COR S.18] WOOD POST - GEORGE ADAIR, D.S. - 1852 - (TAMARACK 5"-N71°E-16 LINKS) (TAMARACK 8"-S30°W-19 LINKS)  
M.S. McNABB-1946-SET WOOD POST-ESTABLISHED PROPORTIONATE DISTANCE BETWEEN CORNERS (CEDAR 7"-EAST 9.5') (CEDAR 5"-N12°W-26')

B-7 [N1/4 COR S.19] WOOD POST - GEORGE ADAIR, D.S. - 1852 (BEECH 6"-N26°W-23 LINKS) (BEECH 7"-S46°E-18 LINKS)  
NO RECORD EVIDENCE OF SUBSEQUENT CORNER RECOVERY OR MONUMENTATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
B-5 [N1/4 COR S.18] CHAINED EAST FROM NW COR SEC 18 @ 1265' M/L FOUND McNABB'S 1946 N1/16 COR (CEDAR POST SCRIBED 1/8) AND A 2585' M/L FOUND REMAINS OF McNABB'S WOOD POST & HIS CEDAR BT (EAST 9.5') WHICH IS STILL GREEN. ACCEPTED EXISTING MONUMENT AS BEING A CAREFULL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

B-7 [N1/4 COR S.19] FOUND IN PLACE, AS INDICATED BY E-W COUNTY ROAD IMPROVEMENTS & N-S OCCUPATION AN IRON BOLT, ORIGIN UNKNOWN. CORNER POSITION CHECKS WELL TO OCCUPATION TO THE EAST & WITH GLO DISTANCES TO ADJOINING CORNERS E & W. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-5 REPLACE WOOD POST W/A BERNTSEN ALNB30 ALUMN MONUMENT WITH THE CAP STAMPED TO ID THE CORNER POSITION.  
TAMARACK 6" CEDAR 10" TAMARACK 9" TAMARACK 9" SURVEY MONUMENT SIGN POST  
N3°W EAST S9°W N82°W NORTH  
36.42' 9.50' 24.98' 20.59' 1.93' (TO FACE)

B-7 SET, OVER EXISTING MON, A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE COR POSITION & RAISED TO RD SURFACE W/A MON BOX  
MAPLE 20" POWER POLE SURVEY MONUMENT SIGN POST  
N6°E S37°E SOUTH  
65.06' 36.64' (TO FACE) 22.45' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC - DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. Davis Date 7/11/94  
Surveyor's Michigan License No. 16926