

SURVEY & REMONUMENTATION

DEC 07 1993

COMMISSION

Approved by Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On Sept 23, 1993
Robert E. Schaefer
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in DELTA (County)

1. Public Land Survey	T <u>38</u> N R <u>24</u> W	Corner Code # <u>C-2</u> <u>C-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____
SW COR SEC 5 & 1/4 COR COMMON TO SEC'S 5 & 6

LIBER 7 Pg 306

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, M.P. DAVIS, in a field survey on AUGUST, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-3 [SW COR SEC 5] WOOD POST GEORGE ADAIR 1852 (SUGAR 10°-N18°W-11 LINKS) (BEECH 6°-S20°E-18 LINKS) D.A. BROTHERTON-1907-IDENTIFIED FROM ORIGINAL BT'S (TEL. POLE WEST 71') M.S. McMANN-1933-ROAD SURVEY FOR BARK RIVER TWP. FOUND WOODSTAKE INPLACE (W. BIRCH 8°-N19°W-34.4') (POWER POLE-NORTH-21.4') SET IRON PIN
- C-2 [1/4 COR COMMON TO SEC'S 6/5] WOOD POST-GEORGE ADAIR-1852 (BEECH 8°-N44°E-10 LINKS) (BEECH 7°-S79°W-20 LINKS) M.S. McNABB-1933-IDENTIFIED CORNER POSITION BY WOOD POST FOUND IN ROADBED-REPLACED WITH IRON PIPE-(MAPLE 7°-EAST-26.0') (ELM 6°-N52°W-26.4' [NO MENTION IN McNABB RECORDS OF ORIGINAL EVIDENCE FOUND])

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-3 [SW COR SEC 5] FOUND THIS DATE McNABB'S 1933 IRON PIN 28" BELOW ROAD SURFACE. ACCEPTED EXISTING MONUMENT AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
- C-2 [1/4 CORNER COMMON TO SEC'S 6/5] FOUND THIS DATE McNABB'S 1933 IRON PIPE. ACCEPTED EXISTING MONUMENT AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-3 SET, INSIDE OF A MONUMENT BOX, A 5/8" X 18" REBAR W/A 3-1/4" ALUMINUM CAP STAMPED TO IDENTIFY THE CORNER POSITION.
SE ANCHOR BOLT NW ANCHOR BOLT NW ANCHOR BOLT
RR X-ING SIGNAL BASE RR X-ING SIGNAL BASE RR X-ING SIGNAL BASE
S62°W - 34.29 S26°W - 42.47' N76°W - 15.24
- C-2 REPLACED EXISTING IRON PIPE W/A 5/8" X 18" REBAR WITH A 3-1/4" ALUMINUM CAP STAMPED TO IDENTIFY THE CORNER POSITION AND SET INSIDE OF A MONUMENT BOX.
ELM 18" BEECH 12" IRONWOOD 13" MAPLE 18" ALUMINUM SIGN POST
N49°E S53°E S42°W S85°W WEST
57.00' 55.95' 63.80' 45.70' 33.0' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC - DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE.

Signed by M.P. Davis Date 9/22/93

Surveyor's Michigan License No. 16926