

SURVEY & REMONUMENTATION

OCT 26 1995

COMMISSION

78

Approved by Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On June 6, 1995
Shirley Blahut
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
DELTA
(County)

Located In: Corner Code #

- | | | | | | |
|------------------------------------|---|-------------|---|-------------|-----|
| 1. Public Land Survey | T | <u>38</u> N | R | <u>24</u> W | D-3 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

Recorded JUN 13 1995
9:00 A.M. in Liber 8 Page 78
at _____ o'clock in _____
_____ Reg. of Deeds.
Delta County, Michigan
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims D-3 [N1/4 COR S.8]

I, M.P. DAVIS, in a field survey on June, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
D-3 [N1/4 COR S.8] WOOD POST - GEORGE ADAIR, D.S. - 1852 (CEDAR 7"-N55°W-18 LINKS) (CEDAR 8"-S61°E-10 LINKS)
1933 DELTA COUNTY ROAD COMMISSION RECORDS INDICATE CORNER IN PLACE
M. DAVIS, RLS - FOUND I.P. 24" BELOW COUNTY ROAD SURFACE - RAISED TO GRADE W/A MONUMENT BOX & I.P. W/A SURVEY CAP [NO WIT'S]
1982-M.D.O.T. RECORDS-FOUND I.P. IN PLACE (POWER POLE-N37°W-43.69') (COR FENCE POST-NORTH-31.31) (TELE POLE-S75°W-50.07')
RECORDED IN LIBER 5 OF LCR'S ON PAGE 94.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
D-3 [N1/4 COR S.8] FOUND IN PLACE THE ABOVE MENTIONED MONUMENT. REPLACED EXISTING I.P. WITH A 5/8" X 18" REBAR & A 3 1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION. CORNER POSITION IS 10.26' NORTH AND 0.67' EAST OF MIDPOINT BETWEEN SECTION CORNERS FOUND E & W. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
D-3 SET INSIDE EXISTING MONUMENT BOX A 5/8" X 18" REBAR & A 3 1/4" ALUMN CAP STAMPED TO ID THE COR POSITION
POWER POLE CORNER FENCE POST SURVEY MONUMENT SIGN POST NO OTHER WIT'S AVAILABLE
N38°W NORTH SOUTH
43.23 (TO FACE) 31.61' (TO FACE) 17.89' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC - DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. Davis Date 6/3/95
Surveyor's Michigan License No. 16926