

**OCT 26 1995
COMMISSION**

Approved by Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On June 6, 1995

[Signature]
Acting Chairman

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in DELTA (County)
Located In: _____ Corner Code #

1. Public Land Survey	T	<u>38 N</u>	R	<u>24 W</u>	<u>E-6</u> <u>(E-7)</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	_____
	S	_____	T	_____	_____

Recorded JUN 13 1995
9:00 A.M. in Liber 8 Page 83
Delta County, Michigan
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims E-6 [W1/4 COR S.16] E-7 [NW COR S.21]

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, M.P. DAVIS, in a field survey on MAY, 19 95
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
E-6 [W1/4 COR S.16] WOOD POST - GEORGE ADAIR, D.S. - 1852 - (HEMLOCK 08"-N63"E-11 LINKS) (CEDAR 24"-S60"W-07 LINKS)
M.DAVIS-1979-IDENTIFIED COR POSITION AT JCT. OF FENCE LINES N-S & E-W - FROM TESTIMONY OF JOSEPH MADALINSKI LONG TIME RESIDENT OF THE AREA, THAT PRIOR TO THE CONSTRUCTION OF THE FENCE LINES A SCR'D SQ'D POST STOOD AT WHAT IS NOW THE JCT OF THE FENCE LINES - SET I.P. AT THIS POSITION (BALSAM 9"-N57"E-10.75') (BALSAM 5"-S33"E-51.95')
1882 RECORDS OF C.E. BROTHERTON INDICATE CORNER IN PLACE - NO DESCRIPTION OF MONUMENT GIVEN OR BT'S NOTED.

E-7 [NW COR S.21] WOOD POST - GEORGE ADAIR, D.S. - 1852 (CEDAR 12"-CORNER TREE) (CEDAR 14"-S82 1/2"E-29 LINKS)
1882 RECORDS OF C.E. BROTHERTON SHOW CORNER IN PLACE - NO WIT'S NOTED OR DESCRIPTION OF EXISTING MONUMENT GIVEN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
E-6 [W1/4 COR S.16] RECOVERED 2' I.P. AS ESTABLISHED IN 1979 BY MYSELF & RECORDED IN LIBER 2 OF LCR'S ON PAGE 369. BOTH BALSAM BT'S AS NOTED ARE NOW STUMPS. ACCEPTED THIS POSITION AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE POSITION OF THE ORIGINAL CORNER.

E-7 [NW COR S.21] NO CORNER EVIDENCE FOUND. RESTORED CORNER POSITION FROM ANCIENT LINES OF OCCUPATION & E-W COUNTY ROAD IMPROVEMENTS. OCCUPATION (FARM FENCES) LINES CORRESPOND WITH C.E. BROTHERTON'S 1882 SUBDIVISION OF SEC 17. ACCEPTED THIS POSITION AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6 SET, OVER EXISTING MONUMENT, A BERNTSEN ALNB30 ALUMN MON WITH THE CAP STAMPED TO ID THE CORNER POSITION.
CEDAR 8" CEDAR 6" ELM 5" SURVEY MONUMENT SIGN POST
N12"E S52"E S17"W WEST
39.09' 49.47' 9.13' 2.44' (TO FACE)

E-7 SET 5/8" X 18" REBAR W/A 3 1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION.
ELM 6" SURVEY MONUMENT SIGN POST NO OTHER WIT'S AVAILABLE - IN BOTTOMS LANDS
N82"E SOUTH OF THE BARK RIVER
94.10' 20.30' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC - DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. Davis Date 6/3/95
Surveyor's Michigan License No. 16926