

OCT 26 1995 COMMISSION

Approved by Delta County Land Survey Remonumentation Peer Group Under Act 345 Of P.A. Of 1990 On June 6, 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Form for recording corners with fields for 'Public Land Survey', 'Property Controlling in Section', 'Miscellaneous Property in Sec.', 'Lot No.', and 'Private Claims'. Includes corner codes G-11 and G-12.

Recorded JUN 13 1995 9:00 A.M. 8 86 Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 1-13. Contains numerical data points for recording corners.

I, M.P. DAVIS in a field survey on APRIL 19 95 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: G-11 [NW COR S.34] GEORGE ADAIR, D.S. - 1852- WOOD POST - (BEECH 12'-N55'E-57 LINKS) (BEECH 08'-S10'W-43 LINKS) M.S.McNABB-1917-FOUND STAKE IN PLACE-NO WIT'S NOTED M.S.McNABB-1922-FROM PREVIOUS SURVEY-SET IRON STAKE (CORNER FENCE POST-N40'W-25.7') (POWER POLE-N41'E-24.2') M.S.McNABB-1931-IRON STAKE & BT'S FROM PREVIOUS SURVEY IN PLACE G-12 [W1/4 COR S.34] GEORGE ADAIR, D.S. - 1852 - WOOD POST - (BEECH 12'-N56'W-24 LINKS) (CEDAR 14' -S30'E-22 LINKS) M.S.McNABB-1922-NO EVIDENCE OF ORIGINALS-SET 1/2 DISTANCE BETWEEN CORNERS (HEMLOCK STUMP 24'-S63'W-16.7') (FENCE POST-N37'E-14.5')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: G-11 [NW COR S.34] FOUND IN PLACE A 3/4" IRON PIN. McNABB'S BT'S HAVE SINCE BEEN REMOVED. ID EXISTING MONUMENT AS BEING THE PROPER POSITION BY PARTIAL RETRACEMENT OF McNABB'S 1932 ROAD ALIGNMENT SURVEY OF COUNTY ROAD 535. ACCEPTED EXISTING MONUMENT AS THE BEST AVAILABLE EVIDENCE AS TO THE POSITION OF THE ORIGINAL CORNER. G-12 [W1/4 COR S.34] NO EVIDENCE OF McNABB'S 1922 CORNER MONUMENT OR ACCESSORIES FOUND. RESTORED CORNER POSITION BY RECOVERY OF McNABB'S IRON PIPE N1/16 COR ON WEST LINE OF SEC 34 AND EXTENDING A LINE SOUTH FROM THE NW COR OF SEC 34 THRU THE N1/16 & SETTING THE 1/4 CORNER ON THIS LINE AT A PROPORTIONATE DISTANCE SOUTH OF THE N1/16. THIS PLACES THE 1/4 COR 1.56' SOUTH & 1.20' WEST OF THE MIDPOINT BETWEEN SEC COR'S. AS THIS FITS EXISTING FARM OCCUPATION, I HAVE ACCEPTED THIS POSITION AS BEING A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: G-11 SET, OVER EXISTING MONUMENT, A BERNTSEN AINB30 ALUMN MON WITH THE CAP STAMPED TO ID THE CORNER POSITION. POWER POLE N36'E 33.71' (TO FACE) USGS MONUMENT N89'E 21.76' SURVEY MONUMENT SIGN POST SOUTH 3.38' (TO FACE) NOTE: CORNER POSITION SURROUNDED BY FARM LANDS AND COUNTY ROAD IMPROVEMENTS NO OTHER WIT'S AVAILABLE. G-12 SET A BERNTSEN AINB30 ALUMN MONUMENT WITH THE CAP STAMPED TO ID THE CORNER POSITION. MAPLE 9" N64'E 10.18' MAPLE 12" S12'E 43.06' SURVEY MONUMENT SIGN POST EAST 2.48' (TO FACE) NOTE: NW & SW QUAD'S ARE OCCUPIED BY CULTIVATED FARM LANDS. NO OTHER WIT'S AVAILABLE.

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC-DISTANCES ARE TO A NAIL W/A DELTA COUNTY REFERENCE TAG, UNLESS NOTED OTHERWISE

Signed by M.P. DAVIS Date 6/3/95 Surveyor's Michigan License No. 16926