

FEB 22 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 1/17, 1996
Robert Schumling
acting chairman

For corners in
DELTA
(County)

Located In: Corner Code #

- 1. Public Land Survey T 38 N R 24 W H-7 & H-11
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Recorded Jan 18 1996
at 9:00 o'clock AM in Liber 8 Page 119
Robert C. Thoms Reg. of Deeds.
Delta County, Michigan

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims H-7 [N1/4 COR S.22] H-11 [N1/4 COR S.34]

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, M.P. DAVIS, in a field survey on 12/95 7/94, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
H-7 [N1/4 COR S.22] GEORGE ADAIR, D.S. - 1852 - WOOD POST - (TAMARACK 04°-N75°W-18 LINKS) (SPRUCE 03°-S45 1/2°E-45 LINKS)
NO RECORD EVIDENCE OF SUBSEQUENT CORNER RECOVERY OR MONUMENTATION
- H-11 [N1/4 COR S.34] GEORGE ADAIR, D.S. - 1852 - WOOD POST - (CEDAR 10°-N81°E-09 LINKS) (HEMLOCK 10°-S81°W-09 LINKS)
NO RECORD EVIDENCE OF SUBSEQUENT CORNER RECOVERY OR MONUMENTATION

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
H-7 [N1/4 COR S.22] NO CORNER EVIDENCE FOUND. SET CORNER AT MIDPOINT BETWEEN SECTION CORNERS 1/2 MILE EAST AND WEST. CORNER IS LOCATED IN A DENSE SPRUCE/TAMARACK SWAMP, 12' N/L NORTH OF A E-W WOODS ROAD.

H-11 [N1/4 COR S.34] NO CORNER EVIDENCE FOUND. REESTABLISHED CORNER POSITION FROM ANCIENT LINES OF OCCUPATION. EXTENDED LINE EAST FROM NW COR OF S.34 THRU CORNER FENCE POST FOUND AT THE W1/16 (FENCE LINE E-W & S) AND SET THE 1/4 CORNER ON THIS LINE AT A DISTANCE EAST OF THE W1/16 THAT IS EQUAL TO THE DISTANCE THAT THE W1/16 IS EAST OF THE NW CORNER OF S.34. ACCEPTED THIS POSITION AS THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7 SET BERNTSEN AINB30 ALUMN. MONUMENT W/A 3 1/4" CAP STAMPED TO ID THE CORNER POSITION.
SPRUCE 3" SPRUCE 4" SPRUCE 3" SPRUCE 4" SURVEY MONUMENT SIGN POST
N38°W N63°E S54°E S63W° NORTH
17.62' 10.76' 12.60' 10.25' 2.73' (TO FACE)

H-11 SET BERNTSEN AINB30 ALUMN MONUMENT W/A 3 1/4" CAP STAMPED TO ID THE CORNER POSITION.
MAPLE 11" SPRUCE 6" W. BIRCH 8" SURVEY MONUMENT SIGN POST
NORTE S10°W. S64°W S73°E.
27.84' 19.63' 20.43' 2.24' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC - DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. Davis 1/18/96 Date JAN 9, 1996
Surveyor's Michigan License No. 16926