

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 38. NR. 24. W

Delta COUNTY

DESCRIPTION OF CORNER Section corner common to Section 23, 24, 25, and 26

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 10" White Pine (S 26 NBT) S 75° W 55 Links

10" White Pine (S 25 NBT) S 20° E 64 Links

10" Red Pine (S 24 NBT) N 16° E 59 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR  
RESTORED. This corner was replaced from two Red Pine B. T.'s both are stumps in  
poor condition. Corner found by H. Smith and shown to us by E. Dahlvik, Escanaba.

Corner lies on Red Pine Ridge. Squared and scribed 6" Red Pine 05 Links S E of  
corner.

Corner was placed and witnessed with Dahlvik and J. Bastian.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 2/23/60  
REGISTERED LAND SURVEYOR  
Billy D. Buckler