

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Delta COUNTY


T 38 N R 24 W

DESCRIPTION OF CORNER 1/4 corner for sections $\frac{26}{35}$

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 6/10/69, F. J. Bray

WITNESSES TO CORNER..... 14" W. Pine (1/4 S) (NBT) N 69° W, 42 links



8" Cedar (1/4 S) (NBT) N 78° E, 47 links

McNabb's - 8" Cedar (BT) S 30° W, 23 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from wood post and old rotted scribed post. Possibly set by M. McNabb in 1924. He mentioned original maple B.T. in 1924. No evidence of tree at the present time. Rotted pine stump checks for other B.T. Blazed trees near.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE

6/25/69

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68