

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>38</u> N. <u>X</u> , R. <u>24</u> W.	<u>K-2</u>
2. PROPERTY CONTROLLING IN SECTION <u>2</u>	T. <u>38</u> N. <u>X</u> , R. <u>24</u> W.	<u>3,10</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER _____

I, Frank J. Bray do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on June 1 1973 established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

K-2 Woodpost:

Cedar	12	N46°W	22 links
Cedar	8	S36°E	45 links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-2 This corner was set from 3 old post points and remains at Marcus McNab witnesses. McNab witnesses, Tam. 6 NNE 13', Tam. 7 SW by W 23.4'.**
- 3 This corner was set by proportionate measurement on a line between section corner north and 1/4 corner to the south.**
- 10 This corner was set by mid-point and on a line between section corners south and 1/4 corner north.**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-2 1" iron pipe with 4" aluminum cap. 3 & 10 1/2" pipe All bearings-magnetic**
- | | | | | | |
|-----|--------------|----------|-------|-------|-------|
| K-2 | 1/4 Cedar | (1/8) | (NBT) | S76°E | 10.8' |
| | 10" Tamarack | (1/8) | (NBT) | N20°E | 16.6' |
| 3 | 4" Cedar | (N 1/16) | (BT) | S69°E | 8.1' |
| | 4" Cedar | (N 1/16) | (BT) | N08°W | 19.0' |
| 10 | 4" Cedar | (S 1/16) | (BT) | N39°E | 7.3' |
| | 4" Cedar | (S 1/16) | (BT) | S16°E | 0.5' |

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY: Frank J. Bray CHIEF OF SURVEY PARTY DATE 6/13/73

MICHIGAN REGISTERED LAND SURVEYOR (SEAL)