

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>38</u> <sup>N.</sup> / <sub>S.</sub> R. <u>24</u> <sup>K.</sup> / <sub>W.</sub>	<u>K-7, K-8, L-7</u>
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER \_\_\_\_\_

I, Frank J. Bray do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on May 29 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

<b>K-7 Woodpost:</b>	<b>Hemlock</b>	<b>11</b>	<b>N 31° W</b>	<b>36 links</b>
	<b>Hemlock</b>	<b>22</b>	<b>S 17° E</b>	<b>23 links</b>
<b>K-8 Woodpost:</b>	<b>Hemlock</b>	<b>11</b>	<b>N 47° W</b>	<b>25 links</b>
	<b>Hemlock</b>	<b>10</b>	<b>S 34° E</b>	<b>27 links</b>
<b>L-7 Woodpost:</b>	<b>Cedar</b>	<b>6</b>	<b>N 41° W</b>	<b>16 links</b>
	<b>Tamarack</b>	<b>7</b>	<b>S 66° E</b>	<b>9 links</b>

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-7** This corner was set by double proportionate measurement from corners  $\frac{1}{2}$  mile north, 1 mile south,  $\frac{1}{2}$  mile east and 1 mile west. Corner lies 29.0' at center line of winter rd.
- K-8** This corner was set mid-point and on a line between section corners north and south. No evidence of original corner.
- L-7** This corner was set from two original bearing tree stumps. Both in poor condition, scribe marks and axe marks visible.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

All bearings are magnetic  
All 1" iron pipe with 1/2" aluminum cap

<b>K-7</b>	<b>5" Cedar (S24) (NBT)</b>	<b>S33° E</b>	<b>11.1'</b>
	<b>6" Cedar (S23) (NBT)</b>	<b>S57° W</b>	<b>12.1'</b>
<b>K-8</b>	<b>1 1/2" Red pine (1/8) (NBT)</b>	<b>N25° E</b>	<b>23.2'</b>
	<b>1/2" Hemlock (1/8) (NBT)</b>	<b>S 7° W</b>	<b>9.5'</b>
	<b>3" Hemlock (Squared &amp; scribed for post)</b>	<b>S66° E</b>	<b>2.1'</b>
<b>L-7</b>	<b>4" Cedar (1/8) (NBT)</b>	<b>N60° W</b>	<b>10.5'</b>
	<b>5" Cedar (1/8) (NBT)</b>	<b>S80° W</b>	<b>11.8'</b>

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ CHIEF OF SURVEY PARTY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Frank J. Bray MICHIGAN REGISTERED LAND SURVEYOR DATE 4/13/73 (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 13575