

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. <u>38N</u> ^{N.} S. R. <u>24</u> ^{E.} W.	<u>I-4, I-5</u>
2. PROPERTY CONTROLLING IN SECTION <u>11</u>	T. <u>38</u> ^{N.} S. R. <u>24</u> ^{E.} W.	<u>10</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} S. R. _____ ^{E.} W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Frank J. Bray do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 6 1973 established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- I-4 Woodpost:**
- | | | | |
|--------|---|-------|----------|
| Spruce | 5 | N65°E | 20 links |
| Spruce | 4 | S65 W | 5 links |
- I-5 Woodpost:**
- | | | | |
|----------|----|-------|----------|
| Tamarack | 8 | N67°E | 18 links |
| Cedar | 11 | S48°W | 13 links |
- Subsequent monument: 2 woodposts.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-4 This corner was set mid-point and on a line between section corners north and south.**
- I-5 This corner was set from 2 old post bottoms and remains at probable cedar original witness. Collus visible but no scribe or axe marks. Witness snag not on record. 5" tam. N43°W 5.9'.**
- 10 This corner was set mid-point and on line between section corner south and ¼ corner north.**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|--|---------------------------------------|--|
| I-4 1" pipe with 4" aluminum cap. | I-5 1" pipe with 4" brass cap. | |
| 10 1½" pipe | All bearings are magnetic. | |
- | | | | |
|------------|-----------------------|-------------|-------|
| I-4 | 4" Tamarack (¼S) | (NBT) N73°E | 2.2' |
| | 3" B. Spruce (¼S) | (NBT) S08°W | 11.4' |
| I-5 | 5" Cedar (S10) | (NBT) N37°W | 7.6' |
| | 5" Cedar (S15) | (NBT) S10°W | 5.3' |
| 10 | 5" Tamarack (S 1/16) | (BT) S19°E | 11.8' |
| | 4" B. Spruce (S 1/16) | (BT) S31°W | 9.0' |

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Frank J. Bray CHIEF OF SURVEY PARTY DATE 6/13/73 (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 13575