

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 38 N. S. R. 24 W.	I-11, I-12
2. PROPERTY CONTROLLING IN SECTION	35, T. 38 N. S. R. 24 W.	2
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Frank J. Bray do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on May 30 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

I-11 Woodpost:				
W. Pine	26	N52°E	7 links	Subsequent monument; two woodposts
Hemlock	12	S45°W	19 links	
I-12 Woodpost:				
Tamarack	9	N79°W	18 links	
Tamarack	12	S27½°E	31 links	

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I-11 This corner was set from 2 old post in position. Remains of probable witness, two tip cuts in proper position

I-12 This corner was mid-point and on a line between section corners north and south. No original evidence found.

2 This corner was placed midway and on a line between the section corner to the east and ¼ corner to the west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

All bearings are magnetic

I-11 1" iron pipe with ¼" aluminum cap. **I-12** 1" iron pipe with brass cap 4"

2 1" iron pipe with ¼" aluminum cap.

I-11	5" Cedar	(S27)	(NBT)	N78°W	10.5'
	4" Cedar	(S34)	(NBT)	S45°W	10.5'
I-12	6" Cedar	(1/3)	(NBT)	S10°E	1.8'
	6" Cedar	(1/3)	(NBT)	N47°W	13.1'
2	7" Cedar	(E 1/16)	(BT)	N70°E	5.8'
	8" Cedar				

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Frank J. Bray MICHIGAN SURVEYOR DATE 6/13/73 (SEAL)

13575