

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>38</u> N. R. <u>24</u> W.	<u>I-3, J-3</u>
2. PROPERTY CONTROLLING IN SECTION	<u>11</u> , T. <u>38</u> N. R. <u>24</u> W.	<u>2</u>
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Frank J. Bray do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 1 1973 established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

I-3 Woodpost:

Spruce	5	S39 ¹ / ₂ °W	21 links
Spruce	4	N39°E	15 links

J-3 Woodpost:

Aspen	18	N71°E	24 links
Aspen	16	S50°W	13 links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I-3 This corner was set by double proportionate measurement from corners 1 mine north and southeast and west.

J-3 This corner was set mid-point and on a line between section corners east and west. No original evidence found.

2 This corner was set mid-point and on a line between section corners east and ¹/₄ corner west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-3 1" pipe with 4" aluminum cap. **J-3** 1¹/₂" pipe **2** 1¹/₂" pipe with brass coupling
All bearings are magnetic.

I-3	9" B. Spruce (82)	(NBT)	N76°E	12.4'
	4" B. Spruce (83)	(NBT)	N70°W	8.9'
J-3	10" H. Maple (1/8)	(NBT)	N20°W	9.0'
	9" H. Maple (1/8)	(NBT)	S25°E	12.2'
2	5" Cedar (E 1/16)	(BT)	N18°E	10.6'
	9" Cedar (E 1/16)	(BT)	S69°W	15.6'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Frank J. Bray CHIEF OF SURVEY PARTY DATE 6/13/73
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 13575