

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 38 N. R. 24 W.	G-3, H-3
2. PROPERTY CONTROLLING IN SECTION	10 T. 38 N. R. 24 W.	2
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. S. W.	
4. LOT NO.	RECORDED PLAT	
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Frank J. Bray do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 5 1973 established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**G-3 Woodpost:** Beech 13 N03°W 12 links  
 Beech 10 S10°E 17 links  
 Subsequent monument; 1" iron pin

**H-3 Corner tree,** Spruce 4  
 Spruce 6 N30°E 30 links

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**G-3** This corner was set from notes of Marcus McNab-found 1" iron pin in place. Corner lies in junction at roads east & west and road north. Fence line south.

**H-3** This corner was set mid-point and on a line between section corners east & west. No evidence of original corner. Corner lies 14.0' south of winter Rd. center line.

**2** This corner was set mid-point and on a line between 1/4 corner west and section corner east. Corner lies on south edge of ridge.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

All bearings are magnetic

<b>G-3</b>	3" apple tree	S04°W	24.25'	
	9" apple tree	N72°E	77.3'	1" iron pin in place
	power pole	N51°W	46.2'	
<b>H-3</b>	3" B. Spruce (1/8)	(NBT) S44°W	27.4'	
	6" B. Spruce (1/8)	(NBT) S30°E	70.5'	1" pipe 3" aluminum cap
<b>2</b>	4" Cedar (E 1/16)	(BT) N48°E	22.7'	
	10" Cedar (E 1/16)	(BT) S11°E	13.7'	1 1/2" pipe

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Frank J. Bray DATE 6/13/73  
 MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 13575