

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. <u>38</u> ^{N.} S. R. <u>24</u> ^{W.} E.	<u>J-7</u>
2. PROPERTY CONTROLLING IN SECTION <u>23</u>	T. <u>38</u> ^{N.} S. R. <u>24</u> ^{W.} E.	<u>1,2</u>
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. ^{N.} S. R. ^{E.} W.
4. LOT NO., RECORDED PLAT.....		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Frank J. Bray do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on May 22 19 73, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19 .., found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

J-7 Woodpost:

Hemlock	8	N64°W	10 links
B. Ask	14	S74½°E	137 links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

J-7 This corner was set mid-point and on a line between section corners east and west. Old post and rat skin near by. Corner is on north edge of winter road. No original witnesses present.

1 This corner was set mid-point and on a line between section corner to the west and ¼ corner east. Corner lies 21.0' north of center line of wood road.

2 This corner was set mid-point and on a line between section corner east and ¼ corner west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

All bearings are magnetic All 1" iron pipe with 4" aluminum cap.

J-7	7" Cedar	(½S)	(NBT)	S10°W	30.1'
	8" Cedar	(½S)	(NBT)	N18°W	13.3'
1	4" Cedar	(E 1/16)	(BT)	N49°W	28.7'
	3" Hemlock	(E 1/16)	(BT)	N55°E	30.2'
2	4" Cedar	(E 1/16)	(BT)	S15°W	3.3'
	4" Cedar	(E 1/16)	(BT)	N80°W	4.0'

SIGNED BY..... DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY..... CHIEF OF SURVEY PARTY..... DATE

APPROVED AND SIGNED BY: Frank J. Bray MICHIGAN REGISTERED LAND SURVEYOR DATE 6/13/73
Frank J. Bray (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 13575