

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. <u>38</u> N. <u>3</u> R. <u>24</u> W.	<u>K-11, K-12</u>
2. PROPERTY CONTROLLING IN SECTION <u>36</u>	T. <u>38</u> N. <u>3</u> R. <u>24</u> W.	<u>10</u>
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. R. W.
4. LOT NO., RECORDED PLAT.....
5. PRIVATE CLAIMS.....

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Frank J. Bray do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on April 26 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- K-11 Woodpost:**
- | | | | |
|-------|----|--------|----------|
| Cedar | 10 | N44°E | 24 links |
| Cedar | 11 | S60½°W | 25 links |
- K-22 Woodpost:**
- | | | | |
|-------|----|-------|----------|
| Cedar | 10 | East | 80 links |
| Cedar | 11 | S44°E | 20 links |

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-11** This corner was re-established by double proportioned measurement between section corners 1 mile to east and south and ¼ corners ½ mile to the north and west.
- K-12** This corner was placed midway and on a line between section corners to the north and to the south. Woodpost near. No original evidence found.
- 10** This corner was placed midway and on a line between the section corner to the south and ¼ corner to the north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

All 1" iron pipe with 4" aluminum cap All bearings are magnetic.

K-11	7" Cedar (S26)	(NBT)	N66°W	19.2'
	7" Cedar (S36)	(NBT)	S88°E	5.6'
K-12	7" Cedar (¼S)	(NBT)	N40°W	29.5'
	6" Cedar (¼S)	(NBT)	N76°E	35.9'
10	8" Balsam (S 1/16)	(BT)	N42°W	5.5'
	5" Cedar (S 1/16)	(BT)	S65°E	3.5'

SIGNED BY: _____ DATE: _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY: _____ DATE: _____

APPROVED AND SIGNED BY Frank J. Bray DATE 6/13/73
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 13575