

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. <u>38</u> ^N / _S , R. <u>24</u> ^E / _W .	<u>J-1, K-1</u>
2. PROPERTY CONTROLLING IN SECTION <u>2</u>	T. <u>38</u> ^N / _S , R. <u>24</u> ^E / _W .	<u>1</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^N / _S , R. _____ ^E / _W .	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER _____

I, Frank J. Bray do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on June 13 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

J-1 Woodpost:

Fir	6	N83°E	20 links
Sugar	8	N26°W	26 links

K-1 Woodpost:

Lynn	10	N80°E	26 links
Cedar	15	N47°W	16 links
Sugar	12	S44°E	28 links
Beech	14	S15°W	29 links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

J-1 This corner was set mid-point and on a line between section corners east and west. Corner lies in old North and South fence line.

K-1 This corner was set from old fence line south and remains of fence line north. Corner fits well with swamp edges north and south. Corner lies in the approximate center line of County Road.

1 This corner was set mid-point and on a line between section corner west and $\frac{1}{4}$ corner east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1 1" x 1/2" iron bar driven in blacktop. **J-1** 1" iron pipe with 4" brass cap.
1 1 1/2" pipe All bearings are magnetic.

K-1	6"	Cedar	(NBT)	S15°E	39.4'
	5"	Cedar	(NBT)	S45°E	60.7'

J-1	10"	Cedar ($\frac{1}{4}$S)	(NBT)	S69°E	41.2'
	3"	H. Maple ($\frac{1}{4}$S)	(NBT)	N58°E	34.0'

1	9"	Cedar (W 1/16) West	11.0'
	4"	Cedar (W 1/16) N84°E	10.6'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY: Frank J. Bray DATE July 3, 1973
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 13575