

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>38</u> <sup>N.</sup> <del>S.</del> , R. <u>24</u> <sup>E.</sup> <del>W.</del>	<u>K-4</u>
2. PROPERTY CONTROLLING IN SECTION <u>12</u>	T. <u>38</u> <sup>N.</sup> <del>S.</del> , R. <u>24</u> <sup>E.</sup> <del>W.</del>	<u>3,10</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____, R. _____, S. _____, E. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER \_\_\_\_\_

I, Frank J. Bray do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 12 1973 established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

**K-4 Woodpost:**  
 Maple 14 N64°E 35 links  
 Hemlock 15 S67°W 27 links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

**K-4 This corner was set mid-point and on a line between section corners north & south.**

**3. This corner was set mid-point and on a line between section corner north and 1/4 corner south.**

**10. This corner was set mid-point and on a line between section corner south and 1/4 corner north. Corner lies just south of squared cedar.**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**K-4 1" pipe with 1/4" brass esp. 3 & 10 1 1/2" pipe. all bearings are magnetic.**

**K-4 1/4" Hemlock (1/8S) (NBT) S54°E 52.9'**  
**9" Maple, R. (1/8S) (NBT) S49°W 49.7'**

**3 9" Cedar (N 1/16) (BT) N23°E 9.0' 10. 8" Cedar (S1/16) (BT) S45°E 11.1'**  
**4" Cedar (N 1/16) (BT) S78°W 3.8' 6" Cedar (S1/16) (BT) N28°E 8.1'**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Frank J. Bray CHIEF OF SURVEY PARTY DATE July 3, 1973  
 MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

13575