

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 38 N. R. 24 W.	K-5, M-5
2. PROPERTY CONTROLLING IN SECTION	38 N. R. 24 W.	1
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. S. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER \_\_\_\_\_

I, Frank J. Bray do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 8 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
**Woodpost:**

M-5	Balm of Gilead	9	N58°W	21 links
	Cedar	6	S37°W	11 links
	Tamarack	5	N63°E	13 links
	Cedar	10	S10°E	16 links
K-5	Cedar	18	N37°W	32 links
	Cedar	11	S38°E	5 links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

**K-5** This corner was set by double proportionate measurement from corners 1 mile north, west and east and ½ mile south. Corner lies in east & west county rd. Blaze lines north and south.

**M-5** This corner was set by single proportionate measurement from ¼ line fence ½ mile north & section corner 1 mile south. Corner lies at Intersection of Center Line County road north & west. Fence line to south.

1. This corner was set mid-point and on a line between section corner west and ¼ corner east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 All bearings are magnetic. K-5 1½" x 24" pipe. M-5 1½" x 30" pipe

1. 1½" pipe

K-5	5" Cedar (NBT)	S14°W	28.5'	M-5	3" Cedar (NBT)	S 8°E	28.6'
	4" Cedar (NBT)	N50°W	53.0'		4" R. Maple (NBT)	N85°E	42.0'
1.	6" Cedar (W 1/16) (BT)	N80°E	13.7'				
	6" Cedar (W 1/16) (BT)	S06°E	20.7'				

SIGNED BY: \_\_\_\_\_ DATE: \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY: \_\_\_\_\_ DATE: \_\_\_\_\_

APPROVED AND SIGNED BY: Frank J. Bray CHIEF OF SURVEY PARTY DATE: July 3, 1973 (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 13575