

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF --: | LOCATED IN --: | CORNER CODE NUMBER |
|---|--|--------------------|
| 1. PUBLIC LAND SURVEY _____ | T. <u>38</u> N. R. <u>24</u> E. W. | <u>I-6</u> |
| 2. PROPERTY CONTROLLING IN SECTION <u>1/4</u> | T. <u>38</u> N. R. <u>24</u> E. W. | <u>2</u> |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. _____ R. _____ E. _____ S. _____ W. _____ | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Frank J. Bray do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 12 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Woodpost:

I-6
Tamarack 10 N40°W 17 links
Tamarack 6 S44°E 32 links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I-6
This corner was set mid-point and on a line between section corners north and south. Fits well with swamp edge to north. Nonoriginal evidence or signs of occupation.

2.
This corner was set mid-point and on a line between section corners east and 1/4 corner west. Corner lies 39.0' west of fence line north. Robert Makosky remembers that fence was not properly located.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Both. 1" iron pipe with 1/2" aluminum caps.
All readings are magnetic.

I-6 4" Cedar (1/2S) (NBT) N21°E 17.4'
 4" B. Spruce (1/2S) (NBT) N50°W 13.6'
 4" Cedar (1/2S) (NBT) S22°W 9.0'

2. 16" Hemlock (BT) S69°E 66.8'
 6" W. Birch (E 1/16) (BT) N72°E 82.2'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY Frank J. Bray DATE **July 3, 1973**
 MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 13575