

**SURVEY &  
REMONUMENTATION**

**JAN 14 1998**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On October 31, 1997  
*Walter C. Thoren*  
Chairman

For corners in  
DELTA  
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>38 N</u> R <u>19 W</u>	<u>A-06 &amp; A-07</u>
	T <u>38 N</u> R <u>20 W</u>	<u>M-06 &amp; M-07</u>
	T _____ R _____	SAME CORNERS
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Recorded Nov 5 1997  
at 9:00 AM  
Lib. 8 Page 237  
*Walter C. Thoren*  
Recorder

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims A-06 [W1/4 COR S18] A-07 [NW COR S19]

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, M.P. DAVIS, in a field survey on SEPTEMBER, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

A-06 [W1/4 COR S18] J.BURT, D.S. - 1845- WOOD POST- (BEECH 08°-N40°W-34 LINKS) (BEECH 06°-N25°W-47 LINKS) M.S.McNABB-1934-ID CORNER POSITION BY IMPROVEMENTS-SET IRON PIPE AT JCT OF FENCES N-S & E NO WIT'S NOTED

A-07 [NW COR S19] J.BURT, D.S.-1845-WOOD POST (BIRCH 10°-N31°W-14 LINKS) (CEDAR 14°-S26°W-16 LINKS) M.S.McNABB-1934-ID CORNER POSITION BY IMPROVEMENTS, JCT OF FENCES N-S & W (NO WIT'S NOTED) M.DAVIS-1973-SET 3/4" X 18" IRON PIPE WITH A SURVEY CAP-REC'D LIBER 1 OF LAND CORNER RECORDS PAGE 451 (PP S8°E-30.6')(PP S75°E 130.8')(MAPLE N61°E 102.15')

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

A-06 [W1/4 COR S.18] FOUND IN PLACE, A 1 1/4" IRON PIPE AT JCT OF OLD FENCES N-S & E. DISTANCE SOUTH TO SEC CORNER CHECKS WELL WITH THE RECORDS OF McNABB. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE POSITION OF THE ORIGINAL CORNER.

A-07 [NW COR S.19] FOUND IN PLACE IRON PIPE MONUMENT AS SET IN 1973 BY MYSELF AND REC'D IN LIBER 1 OF LAND CORNER RECORDS, PAGE 451. ID CORNER MONUMENT FROM WIT'S NOTED IN 1973 WHICH ARE STILL IN PLACE. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE POSITION OF THE ORIGINAL CORNER.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

A-06 SET OVER EXISTING IRON PIPE A BERNTSEN A1NB30 ALUM MONUMENT WITH THE CAP STAMPED TO ID THE CORNER POSITION.  
 SPRUCE 10" SURVEY MONUMENT SIGN POST NEW N-S FENCE NOTE: FARM FIELDS IN ALL QUADS.  
 NORTH WEST EAST NO OTHER WIT'S AVAILABLE  
 71.60' 1.64' (TO FACE) 15.5'

A-07 SET, OVER EXISTING MONUMENT, A BERNTSEN A1NB303 ALUM MONUMENT WITH THE CAP STAMPED TO ID THE CORNER POSITION.  
 NOTE: BT'S NOTED IN 1973 REPORT ARE STILL IN PLACE SURVEY MONUMENT SIGN POST  
 SOUTH  
 2.30'

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC - DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. Davis Date 10/27/97  
Surveyor's Michigan License No. 16926

