

SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/12, 1996
Robert Schmeling
Chairman

For corners in
DELTA
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>38 N</u> R <u>21 W</u>	<u>A-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Recorded DEC 20 1996
at 2:00 o'clock PM
Liber 8 Page 173
William C. Thoreson
Delta County, MI Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A-2 [W1/4 COR SEC 6]

I, M.P. DAVIS, in a field survey on OCTOBER, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
A-2 [W1/4 COR SEC 6] J. BURT, D.S. - 1845 - WOOD POST (HEMLOCK 06°-N36°W-24 LINKS) (HEMLOCK 09°-S78°W-24 LINKS)
A. MERRYWEATHER - 1846 - POST IN PLACE.
M. MCNABB - 1913 - NO EVIDENCE OF ORIGINALS - MCNABB RESET IRON PIPE AT 1/2 DISTANCE BETWEEN CORNERS NORTH AND SOUTH.
NEW WITNESS (BIRCH - 03" - N60°W - 30.3 FT.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
A-2 [W1/4 COR SEC 6] FOUND MCNABB'S IRON PIPE AND BIRCH WITNESS. BIRCH NOW 12' HIGH SNAG 20" IN DIAMETER. ACCEPTED AS BEING A CAREFULL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-2 SET OVER IRON PIPE A BERNTSEN ALNB36 ALUMINUM MONUMENT W/A 3 1/4" CAP STAMPED TO ID THE CORNER POSITION.
MAPLE 12" CEDAR 04" CEDAR 05" CEDAR 05" SURVEY MONUMENT SIGN POST
N18°E N68°W S69°E S09°W N27°W
27.23' 15.05' 15.89' 14.93' 2.00' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL W/A REFERENCE TAG, UNLESS NOTED OTHERWISE.

Signed by M.P. Davis Date 12/12/96

Surveyor's Michigan License No. 16926