

**SURVEY &
REMONUMENTATION**

MAR 21 1997

COMMISSION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/12, 1996

Robert Schmeling
Acting Chairman

For corners in
DELTA
County,

Located In: Corner Code #

1. Public Land Survey	T <u>38 N</u> R <u>21 W</u>	<u>C-2 & C-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Recorded DEC 20 1996
at 2:00 o'clock PM
Liber B Page 153
Walter C. Thomas
Delta County, MI Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

C-2 [E1/4 COR SEC 6] C-3 [SE COR SEC 6]

I, M.P. DAVIS, in a field survey on OCTOBER, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	•	5	4	3	2	1						
3		•											
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 C-2 [E1/4 COR SEC 6] A. MERRYWEATHER, D.S. - 1848 - WOOD POST (POPLAR 10"-N75°W-19 LINKS) (BALSAM 05"-S65°E-13 LINKS) M. MCNABB - 1913 - WOOD POST - (W. BIRCH 16" - N.60°E.-13.4 FT) (CEDAR 10"-S19°W-18.65 FT)
 C-3 [SE COR SEC 6] A. MERRYWEATHER, D.S. - 1848 - WOOD POST (TAMARACK 06"-N25°E-22 LINKS) (TAMARACK 05"-S45°W-35 LINKS) F.T. BURGESS, RLS - 1955 - TIE TO PLAT OF SUNDSTROM SHORES SUBD. REC'D LIBER "B" PG. 85.) - NO NEW WIT'S NOTED

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 C-2 [E1/4 COR SEC 6] NO EVIDENCE OF MERRYWEATHER OR MCNABB CORNER MONUMENT FOUND, ESTABLISHED NEW COR POSITION AT MIDPOINT BETWEEN SECTION COR'S NORTH AND SOUTH. THIS POSITION MATCHES WELL WITH MCNABB'S 1913 DISTANCE BETWEEN THE W1/4 COR AND THE E1/4 CORNER.
 C-3 [SE COR SEC 6] FOUND REMAINS OF METAL LOCATOR TAGS - NO POST LOCATED - RESET COR BY EXTENDING NORTH THE WEST LINE OF THE PLAT OF SUNDSTROM SHORES SUBD. AND SET AT PLAT DISTANCE. THIS POSITION FALLS NEAR THE FOUND LOCATOR TAGS. ACCEPTED AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE POSITION OF THE ORIGINAL CORNER.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 C-2 SET BERNTSEN A1NB30 ALUMN MON WITH THE CAP STAMPED TO ID THE CORNER POSITION.
 CEDAR 7" CEDAR 9" SPRUCE 6" CEDAR 5' SURVEY MONUMENT SIGN POST
 S81°W N21°W S80°E S08°E N61°E
 22.22' 34.21' 33.10' 24.22' 1.99' (TO FACE)
 F-9 SET BERNTSEN A1NB30 ALUMN MONUMENT WITH THE CAP STAMPED TO ID THE CORNER POSITION.
 TAMARACK 7" TAMARACK 4" SPRUCE 4" CEDAR 5" SURVEY MONUMENT SIGN POST
 S87°W N87°E S45°W N35°E NORTH
 29.12' 7.07' 10.50' 25.47' 1.62' (TO FACE)



NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL W/A REFERENCE TAG, UNLESS NOTED OTHERWISE.

Signed by M.P. Davis Date 12/10/96
 Surveyor's Michigan License No. 16926