

JAN 15 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On 3-3, 1999  
David B. Babbitt  
Chairman

For corners in  
DELTA  
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>39</u> N R <u>18</u> W	F - 5
	T <u>39</u> N R <u>18</u> W	F - 7 ✓
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Registration Mar 4 1999  
at 9:00 AM  
Libar 9 Page 150  
William C. Thomas  
Delta County Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

F-5 [N1/4 COR SEC 16] F-7 [N1/4 COR SEC 21]

I, M.P. DAVIS, in a field survey on FEBRUARY, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-5 [N1/4 COR SEC. 16] A.MERRYWEATHER, DS-1848-SET WOOD POST (IRONWOOD 06' N53°W 22 LINKS)(BEECH 10' S20°E 25 LINKS) T.O'BRIEN-1980-SET RR SPIKE IN C/L OF E-W COUNTY ROAD & IN LINE WITH FENCES N-S (PP S73°W 96.2')(ANCHOR BOLT IN FENCE COR N4°E 32.5')

F-7 [N1/4 COR SEC 21] A.MERRYWEATHER, DS-1848-SET WOOD POST-(CEDAR 16' S64°W 17 LINKS)(CEDAR 12' N75°E 25 LINKS) T.O'BRIEN, RLS-1980-L.2 PG. 406 LCR'S-FD IRON SPIKE (FENCE N & S) PP S11°W 41.1' FENCE POST N6°W 32.1'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-5 [N1/4 COR SEC. 16] FOUND IN PLACE, IN APPROX C/L OF E-W COUNTY ROAD AND IN LINE WITH FARM FENCES N-S & RR SPIKE. ID CORNER MONUMENT FROM BT'S REC'D AT L.2 OF LCR'S PG 406. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.

F-7 [N1/4 COR SEC 21] FOUND IN PLACE A 8" IRON SPIKE. ID CORNER MONUMENT FROM BT'S RECORDED IN L.2 OF LCR'S PG.406. CORNER MONUMENT FALLS ON APPROX C/L OF E-W COUNTY ROAD AND IN LINES WITH ANCIENT OCCUPATION LINES N-S. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-5 REPLACED EXISTING MON W/A 5/8" X 18" REBAR W/A 3 1/4" ALUM CAP STAMPED TO ID THE COR POSITION & RAISED TO GRADE W/A MON BOX.  
5/8" X 18" REBAR W/A 2" ALUM WIT CAP CEDAR 05" ASH 05" SURVEY MONUMENT SIGN POST  
N45°E S45°E S63°W N57°W SOUTH  
25.00' 26.54' 69.79' 59.81' 30.80' (TO FACE)

F-7 REPLACED EXISTING MONUMENT W/A 5/8" X 18" REBAR W/A 3 1/4" ALUM CAP STAMPED TO ID THE CORNER POSITION.  
ASH 06" ASH 05" POWER POLE SURVEY MONUMENT SIGN POST  
N14°W N62°E S16°W NORTH  
26.70' 46.55' 41.25' 17.56' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC-DISTANCES ARE TO A NAIL W/A DELTA COUNTY REFERENCE TAG, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 2/15/99

Surveyor's Michigan License No. 16926