

JAN 23 2000

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On Dec 28, 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

M. P. Davis
Acting Chairman

SECTION

For corners in

DELTA (County)	Located In:	Corner Code #
1. Public Land Survey	T 39 N R 18 W	M-02 SAME ✓
	T 39 N R 17 W	A-02 CORNER
	T 39 N R 18 W	M-05 SAME
	T 39 N R 17 W	A-05 CORNER
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

01-04-00
 AT 2:00 O'CLOCK PM
 LIBER 9 PAGE 187
M. P. Davis
 REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

M-02 [E1/4 COR SEC 1] M-05 [NE COR SEC 13]
 4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, M.P. DAVIS, in a field survey on DECEMBER, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-02 [E1/4 COR SEC 1] JOHN BURT, D.S. - 1845-WOOD POST (BEECH 06" N12°W 19 LINKS)(BEECH 14" S75°W 19 LINKS) NO RECORD EVIDENCE OF CORNER RECOVERY AND/OR SUBSEQUENT MONUMENTATION.
- M-05 [NE COR SEC 13] JOHN BURT, D.S. - 1845-WOOD POST (TAMARACK 03 N10°W 19 LINKS)(TAMARACK 03" S61°W 16 LINKS) NO RECORD EVIDENCE OF CORNER RECOVERY AND/OR SUBSEQUENT MONUMENTATION.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-02 [E1/4 COR SEC 1] FOUND IN PLACE A T-IRON WITH RLS CAP #24598 - CORNER MONUMENT WAS PLACED AT THE MIDPOINT BETWEEN AND ON LINE WITH THE SECTION CORNERS 1/2 MILE TO THE NORTH AND SOUTH. ACCEPTED EXISTING MONUMENT AS BEING A CAREFULL AND FAITHFULL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.
- M-05 [NE COR SEC 13] NO CORNER EVIDENCE FOUND. REESTABLISHED THE CORNER POSITION ON LINE WITH AND AT SINGLE PROPORTIONATE DISTANCE BETWEEN THE E1/4 CORNER OF SECTION 12 AND THE E1/4 CORNER OF SECTION 13.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-02 SET, OVER EXISTING MONUMENT, A BERNTSEN A1NB30 ALUM MONUMENT WITH THE CAP STAMPED TO ID THE CORNER POSITION
 W. CHERRY 06" BALSAM 04" ASPEN 05" BALSAM 03" SURVEY MONUMENT SIGN POST
 N40°W S67°E S04°W S75°W N45°E
 15.67' 9.28' 11.44' 15.67' 1.20' (TO FACE)
- M-05 SET A BERNTSEN A1NB30 ALUM MONUMENT WITH THE CAP STAMPED TO ID THE CORNER POSITION.
 CEDAR 08" CEDAR 07" CEDAR 11" CEDAR 08" SURVEY MONUMENT SIGN POST
 N22°W N62°E S33°E S58°W EAST
 17.20' 3.69' 3.66' 19.58' 1.81' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC-DISTANCES ARE TO A NAIL W/A DELTA COUNTY REFERENCE TAG, UNLESS OTHERWISE NOTED.

Signed by M. P. Davis Date 12/23/99
 Surveyor's Michigan License No. 16926