

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 39 N NR. 18 W ..

Delta COUNTY

DESCRIPTION OF CORNER 1/4 Cor. between Sections 32 = 33

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 6" Cedar S 40° E 17 links

"1/4S NBT"

8" Cedar N 72° W 13 links

"1/4S NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 corner from two cedar B.T.'s bearing : S 40° W 10 links
N 80° E 6 links

Both stumps in poor condition, burned and rotted.
Found scribe marks and notch on overgrowth of S.W. B.T.

Squared and scribed 5" cedar at 1/4 Corner.

1/4 Corner found while checking lines run by Carl Makel, District Forester.

SURVEYORS SEAL

SIGNED

Billy J. Buckles
REGISTERED LAND SURVEYOR

DATE 3/22/57