

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 39. NR. 18. W

Delta COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 21, 22, 27,
and 28

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 12" Red Pine (S 27 NBT) S 43° E 42 1/2 Links

5" Cedar (S 29 NBT) S 84° W 33 Links

5" Cedar (S 22 NBT) N 10° E 09 1/2 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR

RESTORED. This corner was re-established from Road intersection one
mile north; road 1 1/2 miles west; Meander corner 26.67 chains east
and Lake Shore to south. No evidence of original corner.

Corner was placed and witnessed October 22, 1959 with Frank J. Bray.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR
Billy D. Buckler

DATE

2/23/60