

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T.39.. NR.18-19.. W

..... D e l t a ..... COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 13, 24, 18, and 19

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap. ....

WITNESSES TO CORNER 9" Cedar (S 24 NBT) S 29° W 71 Links ...

10" Cedar (S 18 NBT) N 18° E 124 1/2 Links

9" Hard Maple (S 13 NBT) N 50° W 68 1/2 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was replaced from one Cedar B. T. bearing S 52° E 19 Links. Cedar is a stub cut 8' high. Scribe marks plain. Corner found by Forestry Division Survey Crew while making a retracement survey of area.

Corner was placed and witnessed October 21, 1959 with Frank J. Bray.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 2/23/60  
REGISTERED LAND SURVEYOR  
Billy D. Buckler