

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 39 N.R. 18 W.


Delta COUNTY

DESCRIPTION OF CORNER Meander corner for Sections 28 and 33

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 9/22/60

WITNESSES TO CORNER..... 8" Cedar (M.C. NBT) S 05° E 22½ Links



7" Cedar (M.C. NBT) S 55° W 39½ Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from M.C. between 33 and 34, N 48° W, a distance of 4.70 chains which is recorded distance and bearing of Meander line. Average length of lines in vicinity was used for length of line between 28 and 33.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 5/31/61
REGISTERED LAND SURVEYOR
Billy D. Buckler