

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 39 N.R. 18 W.


Delta COUNTY

DESCRIPTION OF CORNER Meander corner for Sections 33 and 34

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 9/21/60 with Frank J. Bray

WITNESSES TO CORNER 7" Cedar (M.C. NBT) S 86° W 28 1/2 links



5" Cedar (M.C. NBT) S 43° W 22 1/2 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced at site of Cedar Stump for corner tree. Found 6" cedar bearing N 65° W, 07 Links for B.T. tree still green, found scribe marks "T" on top face and parts of scribe marks, face and notch on bottom. Scribed "BT" on original bearing tree .

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 5/31/61
REGISTERED LAND SURVEYOR
Billy D. Buckler