

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 39 N.R. 18 W.


Delta COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sections 29 and 32

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 9/20/60 with Frank J. Bray.

WITNESSES TO CORNER.....7" Cedar (1/4s NBT) S 34° E 19 Links



6" Cedar (1/4s NBT) N 61° E 58 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed on line with Section Corner 1/2 mile east, and original Cedar line tree 9.50 chains east. Found old blazes at corner but no evidence of Tamarack B.T.'s. Squared and scribed 5" Spruce at corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 5/31/61
REGISTERED LAND SURVEYOR
Billy D. Buckler